APPENDIX C – LOCATIONS LIST

2023 Road Resurfacing – Hot Mix					
Road Name	**From**	**To**	**Work to be Completed**	**Length**	**Road Type**
Burleigh Road N	Dominion Road	Thunder Bay Road	Pulverize and Pave 50mm HL8, 40mm HL3	1,012.00 m	HCB
Point Abino Road North	Fox Road	CN Railway	Pulverize and Pave 50mm HL8, 40mm HL3	600.00 m	HCB
Sims Avenue	Thompson Road	Tenth Street	Pulverize and Pave 50mm HL8, 40mm HL3	208.00 m	HCB
Sims Avenue	Tenth Street	East Dead End	Pulverize and Pave 50mm HL8, 40mm HL3	45.00 m	HCB
Tenth Street	Sims Avenue	Oakes Drive	Pulverize and Pave 50mm HL8 40mm HL3	137.00 m	HCB
Helen Street	Graeber Avenue	Concord Avenue	Pulverize and Pave 50mm HL3	227.00 m	HCB
Helen Street	Concord Avenue	Mathewson Avenue	Pulverize and Pave 50mm HL3	84.00 m	HCB
Helen Street	Mathewson Avenue	Roxborough Avenue	Pulverize and Pave 50mm HL3	60.00 m	HCB
Glendale Avenue	Dovercourt Road	Helen Street	Pulverize and Pave 50mm HL3	170.00 m	HCB
Concord Avenue	Ridge Road S	Helen Street	Pulverize and Pave 50mm HL3	184.00 m	HCB
Kee Lane	Lewis Street	South Dead end	Mill 40mm, Pave 50mm HL3	55.00 m	HCB
Kraft Road	Garrison Road	730 Kraft Road	Mill 40mm, Pave 50mm HL3	1,010.00 m	HCB
Kraft Road	730 Kraft Road	Dominion Road	Pulverize and Pave 50mm HL8, 40mm HL3	1,030.00 m	HCB
			TOTAL	**4,822.00 m**	